

**Bid Specifications for site prep, concrete slab and walkway**

**Please include this initialed checklist with bid.**

**The following are the minimum specifications.**

**Yes   No   Initials**

\_\_\_\_ \_\_\_\_    \_\_\_\_    Site prep & grading, sod stripping & top soil to subgrade, elevation to mimic pool surface under chain link fence. Runoff free flow to 7<sup>th</sup> Street sidewalk.

\_\_\_\_ \_\_\_\_    \_\_\_\_    6" layer of compacted aggregate base.

\_\_\_\_ \_\_\_\_    \_\_\_\_    5" thick concrete slab for shelter area with 12" wide thickened edges and post surrounds with 4ft control expansion joints. All thickened edges and post surrounds concrete to be 8" thick for concrete slab. Reinforced with 3/8" rebar 16" O.C. supported with concrete brick or rebar chairs.

\_\_\_\_ \_\_\_\_    \_\_\_\_    5" thick concrete slab for walkway with 4ft control expansion joints. Reinforced with 3/8" rebar 16" O.C. supported with concrete brick or rebar chairs. Connecting to existing splash pad concrete.

\_\_\_\_ \_\_\_\_    \_\_\_\_    Concrete mix: 3/4" max aggregate and 6 bag mix. Air entrained.

\_\_\_\_ \_\_\_\_    \_\_\_\_    Curing compound per manufacturer's specifications.

\_\_\_\_ \_\_\_\_    \_\_\_\_    Center point of slab to be positioned on center point of building end wall per drawing.